

CONSTRUCTION ACCESSORIES

# PLASTIC SHIM DATASHEET





#### **MONTAGEPLATTE**

#### FREE OF PVC

#### **Application:**

Leveling shims made of plastic as an assembly aid, e.g. when installing prefabricated parts.

#### Installation:

Full-surface, no concentrated point loading. Despite its high stability, no permanent load may be applied. After adjusting the components, they must be lined.



#### Material:

- Polystyrol (PS)
- Free of PVC, CFC, HFC
- Without substances of very high concern according to the candidate list of ECHA (REACH Regulation)

#### Packaging:

Free of halogenated products, azo dye, fire pretection agents.

#### **Order information - MONTAGEPLATTE FULL:**

Item- No.	Thickness mm	Dimension mm	Pcs/ Bag	Pcs/ Big Bag	Pcs/ Pallet
UP02	2	70x70	125	1.000	15.000
UP03	3	70x70	125	1.000	15.000
UP04	4	70x70	125	500	15.000
UP05	5	70x70	125	500	15.000
UP06	6	70x70	125	500	15.000
UP07	7	70x70	125	500	15.000
UP08	8	70x70	125	-	12.000
UP09	9	70x70	125	-	12.000
UP10	10	70x70	125	-	10.000
UP12	12	70x70	125	-	8.000
UP15	15	70x70	50	250	8.000
UP20	20	70x70	50	250	6.000



**Order information - MONTAGEPLATTE LIGHTWEIGHT:** 

Item-	Thickness	Dimension	Pcs/	Pcs/	Pcs/
No.	mm	mm	Bag	Big Bag	Pallet
UP09N	9	70x70	125	-	12.000
UP10N	10	70x70	125	-	10.000
UP15N	15	70x70	50	250	8.000
UP20N	20	70x70	50	250	6.000



lightweight



#### **MONTAGEPLATTE**

#### **Order information - MONTAGEPLATTE:**

Item- No.	Thickness mm	Dimension mm	Pcs/ Bag	Pcs/ Pallet
UPS02	2	70x70	125	15.000
UPS03	3	70x70	125	15.000
UPS05	5	70x70	125	15.000
UPS07	7	70x70	125	15.000
UPS09	9	70x70	125	12.000
UPS10	10	70x70	125	10.000
UPS12	12	70x70	125	8.000
UPS15	15	70x70	50	8.000



horse shoe



## SDG

### Get in touch

#### HEAD OFFICE

21 Tullygoonigan Industrial Estate Moy Road Armagh BT61 8DR

**Tel:** +44 (0) 28 3752 8999

 ${\tt sdgconstruction} technology.com$ 

#### MONAGHAN OFFICE

Cornacrieve Emyvale Monaghan HY18 XY 46

**Tel:** + 353 (47) 87 295

Email: sales@sdg.ie